



ज्ञानगंगा धरोहर

यशवंतराव चव्हाण महाराष्ट्र मुक्त विद्यापीठ
ज्ञानगंगोत्री, गोवर्धन, नाशिक-४२२२२२

दुरध्वनी-(०२५३)२२३००७२, (क. काया) २२३१७१४/१५, २२३४७१८, २२३००७२

जा. क्र. १७११७

दि. १७/०२/२०२६

प्रती,

विषय : विद्यापीठ आवारात सद्यस्थितीतील 'प्लॅट लायब्ररी' कृषी शेडनेट हाऊस डीसमेंटल करणे, स्ट्रक्चरल साहित्य विद्यापीठातील पर्यायी जागेवर स्थलांतरित करणे, पुन्हा उभारणीसाठी उपलब्ध मुख्य सांगाडा साहित्य वापरून सांगाडा उभारणी, गरजेनुसार आवश्यक नवीन जोडणी साहित्य, शेड नेट पुरवठा करणे व बसविणे आणि प्रचलित मानकानुसार नेट हाऊस उभारणी पूर्ण करणे.

महोदय,

विद्यापीठ आवारात सद्यस्थितीतील 'प्लॅट लायब्ररी' कृषी शेडनेट हाऊस डीसमेंटल करणे, स्ट्रक्चरल साहित्य विद्यापीठातील पर्यायी जागेवर स्थलांतरित करणे, पुन्हा उभारणीसाठी उपलब्ध मुख्य सांगाडा साहित्य वापरून सांगाडा उभारणी, गरजेनुसार आवश्यक नवीन जोडणी साहित्य, शेड नेट पुरवठा करणे व बसविणे आणि प्रचलित मानकानुसार नेट हाऊस उभारणी पूर्ण करणे. कामाचे दर पत्रक सादर करणे या कामासाठी खाली नमुद केलेल्या अटी व शर्ती नुसार सोबत जोडलेल्या कामाचे दरपत्रक मागविण्यात येत आहे.

विषयांकीत कामाच्या अटी व शर्ती खालील प्रमाणे असतील.

- १) प्रत्यक्षात सादर कामाच्या ठिकाणी आपण पाहणी करून आपण आपल्या संस्थेच्या लेटरहेडवर दरपत्रक भरून सिलबंद करून दि 23/02/2026 पर्यंत दुपारी 1.00 वाजेपर्यंत विद्यापीठाच्या बांधकाम कक्षात सादर करावे.
- २) फर्म अशा प्रकारच्या कामांसाठी कृषी विभाग नोंदणीकृत असावी आणि अशा प्रकारच्या कामांचा अनुभव असावा. विषयांकीत काम कार्यादेश मिळाल्या पासून सलग 30 दिवसांत पूर्ण केले पाहिजे.
- ३) काम पूर्ण करण्यास विलंब झाल्यास प्रती दिन रूपये 100/- इतका विलंब आकार आकारण्यात येईल व त्याची वजावट आपणास देय असणाऱ्या रकमेतून करून उर्वरित रकमेचे देयक अदा करण्यात येईल.
- ४) वर उल्लेखलेले दर हे आवश्यक साहित्य, वाहतूक, मजुरी, तूटफूट, वेस्टेज, लोडिंग, अनलोडिंग, विद्यापीठामध्ये वस्तू पोहचविणे, इत्यादी सहीतचे भरावेत व त्यात कोणत्याही कारणास्तव वाढ देय राहणार नाही.
- ५) संपूर्ण काम समाधानकारक रित्या पूर्ण झाल्या वर कामाचेदेयक / देयके मंजूर दरानुसार व नियमानुसार वजावटी करून विद्यापीठास सोयीस्कर अशा बँकेच्या धनादेशाद्वारे अदा करण्यात येईल.
- ६) नियमानुसार लागू असणारा वस्तू व सेवा कर स्वतंत्ररित्या अदा करण्यात येईल.


कार्यकारी अभियंता

Yashwantrao Chavan Maharashtra Open University, Nashik, Maharashtra,

Name of work : Dismantling of existing Plant Library Arch shaped agricultural shade net house and relocating and re-erection of the net house at alternative location including reusing of existing reusable structural pipe members, providing and fixing new foundation, clamps, nuts bolts, accessories, new shade net to cover the arch shaped net house, sliding FRP doors, additional items, fixtures, etc. as per standard practice & as per site condition as may be required in the campus of YCMOU, Nashik

* The firm shall be registered under relevant category and listed under department of Agriculture, Govt of Maharashtra

**Quantities mentioned are approximate and shall be paid as per actual quantity measured /execution. .

** GST applicable shall be paid EXTRA.

Item No.	Description of Item of work	Unit	Approx. Qty	Unit Rate (Excluding GST) Rs./ Unit	Amount (Rs.)
1	<u>Dismantling & removal of existing arch shaped net house from the existing site including all structural members, accessories/fitting</u> (to re-locate at alternative location within the campus and re-erecting the same using GI pipe structural members of same existing dismantled net house structure) including, dismantling of agricultural shade net, profiles, clamps, accessories/ fittings, nut bolts, GI pipe members of arches, purlins, poles from the foundation, FRP sliding door panels, including all, labour, complete. (Item quantity payable: Total Sq.m. of covered floor area dismantled of existing net house measured at ground from hokey to hokey as per measurement)	Sq.m. (Shade Net Area Covered measured as Ground floor area)	544		
2	<u>Providing and installation of GI pipe foundation for arched net house at new alternate location to re-install / re-erect shade net house</u> within the campus, providing and fixing Main pole foundation depth 750mm. Columns are fitted over the ground inserts and bolted to the insert pipes of 50 NB *B*Class GI pipes. The ground inserts shall be with the holdfasts. Length of the insert pipes 1 m. PCC of 1:2:4 of 40 mm aggregate size& filling the pit with 1:2:4 concrete hand mixed with 53-grade cement. Considering the proposed murum filling of 300mm in the area the Foundation blocks should be brought 300mm above the existing ground level. The total effective length of the foundation block with stub shall be 750mm + 300mm i.e. 1050mm. Hence; size of the total concrete block shall be 1050x600x600mm. Inserts and columns should be properly bolted at minimum two places with necessary packing and antirust materials. The concrete foundation should be cured as per the requirement. (Item quantity payable: Total Actual Nos. Main pole of foundations installed / executed for New Net house as per measurement)	Nos.	24		
3	<u>Re-Installation/re-erection of arch shaped agricultural net house structure (as per old structure) as per standard practice using the reusable pipe structural members of old structure like GI poles, purlins, arches, hockey's, tie members, providing and fixing new clamps, fittings, accessories, nuts bolts, etc. as may be required and re-erecting the same at new location on and as per the foundation layout/prefixed dimensions of the arched net house, etc.</u> including (i)providing and fixing of aluminum box profiles & Zigzag high carbon steel springs for fitting nets, C-	Sq. m. (Shade Area Covered measured as Ground floor area)	528		

	shaped, aluminum box profiles (min.180 gm/m), smooth edges, with suitable with two way locking arrangements, profile drill-fitted at every 40cm on existing structure as per requirement with min 20mm self-drilling screws, fixing the above with Zigzag high carbon steel springs for fitting nets for locking in box profiles, min 2.2mm diameter, zinc coated, inserted to fix shade net, complete. (ii) the Net shall cover all the area of the Net House structure including roof, gables, and buried 1 ft in the soil at all borders, etc. as per the existing arrangements, with minor fixtures/fittings accessories, if any, as per the site conditions, including material labour, complete.(Item quantity payable: Total Sq.m. of covered floor area of new net house measured from hokey to hokey at ground level as per measurement)				
4	Providing and fixing UV stabilized new agricultural shading net 50% (Green) on new shade net house including all like aluminum profiles, metallic springs, etc. For Re-Installed Arches of Net house of required widths & lengths for covering from all the sides as per standard practices. Specifications: UV Stabilized woven HDPE Tape net, with 50% shading, (Green) Min 100GSM, IS:16008:2012 , Preferred Make/Brands of the items: B&V / Malmo / Garware / Tuflex / Shalimar / Agri plast. Shading net to be fitted at all sides including arched, sides Including material labour, complete. (Item quantity payable: Total Sq.m.of covered floor area of New net house measured from hokey to hokey at ground level as per measurement)	Sq.m. (Shade Area Covered measured as Ground floor area)	528		
5	Providing & Fixing new polycarbonate door with sliding mechanism for Arched Net House. Specifications: UV stabilized FRP /Polycarbonate & G.I sheet door panels, Min.1mm thick with square pipe frame inside, approved design. Single / Double Leaf door with Single big door of 2m(W)X2m(H) or Double leaf arrangement with 1m(W)x2m(H) each leaf with metallic handles zinc coated channels with sliding mechanism, including (i) fixing of doors panels at appropriate locations, to make clear door entry opening min.1.5m (ii) fix door panels Vertically, additional GI pipe supports to fit if required & assemble new double door panels, new sliders, smooth and operational sliding, including material, labour, complete. (Item quantity payable: Total Actual Nos. of New door (2x2 m) installed.)	Nos	1		
				Total (Rs.)	
				GST.....%	
				G. TOTAL	

I/We, M/s.....

Address.....

do hereby state that we have personally visited the site of works, personally inspected, verified the items of works and understood the scope of work as described above, site conditions and agree execute the whole of the proposed work as given above as per the requirement for the in the campus of YCMOU at Gowardhan, Nashik as described above in item 1 to 5 and according to the terms & conditions mentioned herein for the sum of (Grand Total Rs.....)

In words,(Rs.....)

Sign

Name of Firm.....