



यशवंतराव चव्हाण महाराष्ट्र मुक्त विद्यापीठ
ज्ञानगंगोत्री, गोवर्धन, नाशिक-४२२२२२

दुरध्वनी-(०२५३)२२३००७२, (क. काया) २२३१७१४/१५, २२३४७१८, २२३००७२

जा. क्र : UWD/2025-26/1768

दि: 12/03/26

प्रती,

विषय- विद्यापीठातील शैक्षणिक इमारतीच्या छतावर असलेल्या Construction Joints ची दुरुस्ती करणे, त्यांना वॉटरप्रूफिंग करणे, Ducts चे टाईल काढणे व ग्रेनाईट लावणे व इतर अनुषंगिक कामे करणे ..

महोदय,

विद्यापीठातील शैक्षणिक इमारतीच्या छतावर असलेल्या Construction Joints ची दुरुस्ती करणे, त्यांना वॉटरप्रूफिंग करणे, Ducts चे टाईल काढणे व ग्रेनाईट लावणे व इतर अनुषंगिक कामे करणे या कामासाठी खाली नमुद केलेल्या अटी व शर्ती नुसार सोबत जोडलेल्या कामाचे दरपत्रक मागविण्यात येत आहे.

विषयांकीत कामाच्या अटी व शर्ती खालील प्रमाणे असतील.

- १) प्रत्यक्षात सदर कामाच्या ठिकाणी आपण पाहणी करून आपण आपल्या संस्थेच्या लेटरहेडवर दरपत्रक भरून सिलबंद करून दि. _____ पर्यंत दुपारी 1.00 वाजेपर्यंत विद्यापीठाच्या बांधकाम कक्षात सादर करावे.
- २) विषयांकीत काम कार्यादेश मिळाल्या पासून सलग 30 दिवसांत पूर्ण केले पाहिजे.
- ३) काम पूर्ण करण्यास विलंब झाल्यास प्रती दिन रूपये 100/- इतका विलंब आकार आकारण्यात येईल व त्याची वजावट आपणास देय असणाऱ्या रकमेतून करून उर्वरित रकमेचे देयक अदा करण्यात येईल.
- ४) वर उल्लेखलेले दर हे वाहतूक, मजुरी, तूटफूट, वेस्टेज, लोडिंग, अनलोडिंग, विद्यापीठामध्ये वस्तू पोहचविणे इत्यादी सहीतचे भरावेत व त्यात कोणत्याही कारणास्तव वाढ देय राहणार नाही.
- ५) संपूर्ण काम समाधानकारक रित्या पूर्ण झाल्या वर कामाचेदेयक / देयके मंजूर दरानुसार व नियमानुसार वजावटी करून विद्यापीठास सोयीस्कर अशा बँकेच्या धनादेशाद्वारे अदा करण्यात येईल.
- ६) नियमानुसार लागू असणारा वस्तू व सेवा कर स्वतंत्ररित्या अदा करण्यात येईल.


कार्यकारी अभियंता



विद्यापीठातील शैक्षणिक इमारतीच्या छतावर असलेल्या Construction Joints ची दुरुस्ती करणे, त्यांना वॉटरप्रूफिंग करणे, Ducts चे टाईल काढणे व ग्रेनाईट लावणे व इतर अनुषंगिक कामे करणे

Sr. No.	Description	Quantity	Unit	Rate	Amount
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	44.136	Sqm		
2	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	25.00	Number		
3	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	32.850	Sqm		
4	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	234.808	Sqm		
5	Providing and Applying Reinforcement of Greetextile Membrane admix with white based acrylic polymer. Etc. complete	100.179	Sqm		
6	Providing and Applying water proofing treatment using component white based acrylic polymer coating admix with water complete	134.629	Sqm		
7	Providing and laying telephone black / AmbaWhite / Cadbury brown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame /dado/window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	45.936	Sqm		
8	Providing and fixing in position aluminium fixed window fully glazed of any size as per detailed drawing and as directed by Engineer in charge with all necessary aluminium sections including necessary fixtures and fastening such as 5mm thick clear float glass etc. complete. Note While arriving at the rate of item of item weight at 6.90 Kilogram/ One Square Metre is considered. b) Powder Coated	28.242	Sqm		
9	Providing and fixing Country cut teak wood double or single leaf second class fully panelled door shutter with 35 mm thick style and rail with 25mm thick panels with openable fanlight as per detailed drawings. Excluding the door frame 60mmx100mm stainless steel fixtures and fastening and finishing the woodwork with oil painting 3 coats. (Excluding the door frame)	1.890	Sqm		
10	Surface Preparation: Crack surface shall be cleaned using underwater jet to remove the fungal growth and other foreign materials to enable a clean and visible surface. The item includes the cost of hire charges of all equipment, diving equipment and all charges for divers etc., complete.	21.600	Rmt		
11	Crack Groove Cutting: Groove shall be cut using hand held electrically operated concrete cutting machine of size of 50 mm wide and 75 mm deep on each side of the crack to form as "V" groove all along the crack to fill the polyester resin/ Epoxy putty (horizontal and vertical cracks). After the groove cutting, the concrete shall be removed from the groove using the pneumatic concrete chipping machine to form "V" groove. The item includes the cost of hire charges for all machineries, tools and barges and all labour charges etc., complete.	21.600	Rmt		
12	Core Strengthening of Concrete Structure: Strengthening of concrete structure including grouting of concrete with epoxy, AC-DUR-JE, as detailed in the method statement. Item includes cost of material, labour,	14.000	Number		
13	Providing & applying 2 coats of compatible Polyurethane on epoxy fiber wrapped surface with brush /spray application etc complete.	9.720	Sqm		
TOTAL					