



यशवंतराव चव्हाण महाराष्ट्र मुक्त विद्यापीठ
ज्ञानगंगोत्री, गोवर्धन, नाशिक-४२२२२२

दुरध्वनी-(०२५३)२२३००७२, (क. काया) २२३१७१४/१५, २२३४७१८, २२३००७२

जा. क्र : UWD/2025-26/1765

दि : 12/03/26

प्रती,

विषय - विद्यापीठाच्या स्पर्धा परीक्षा प्रशिक्षण केंद्र, बोपोडी येथील सेमिनार हॉल मधील दुरवस्थेत व तुटलेल्या तळफरशा काढणे, नवीन बेडिंग तयार करून नवीन फरशा बसवणे..

महोदय,

विद्यापीठाच्या स्पर्धा परीक्षा प्रशिक्षण केंद्र, बोपोडी येथील सेमिनार हॉल मधील दुरवस्थेत व तुटलेल्या तळफरशा काढणे, नवीन बेडिंग तयार करून नवीन फरशा बसवणे या कामासाठी खाली नमुद केलेल्या अटी व शर्ती नुसार सोबत जोडलेल्या कामाचे दरपत्रक मागविण्यात येत आहे.

विषयांकीत कामाच्या अटी व शर्ती खालील प्रमाणे असतील.

- १) प्रत्यक्षात सदर कामाच्या ठिकाणी आपण पाहणी करून आपण आपल्या संस्थेच्या लेटरहेडवर दरपत्रक भरून सिलबंद करून दि.----- पर्यंत दुपारी 1.00 वाजेपर्यंत विद्यापीठाच्या बांधकाम कक्षात सादर करावे.
- २) विषयांकीत काम कार्यादेश मिळाल्या पासून सलग 30 दिवसांत पूर्ण केले पाहिजे.
- ३) काम पूर्ण करण्यास विलंब झाल्यास प्रती दिन रूपये 100/- इतका विलंब आकार आकारण्यात येईल व त्याची वजावट आपणास देय असणाऱ्या रकमेतून करून उर्वरित रकमेचे देयक अदा करण्यात येईल.
- ४) वर उल्लेखलेले दर हे वाहतूक, मजुरी, तूटफूट, वेस्टेज, लोडिंग, अनलोडिंग, विद्यापीठामध्ये वस्तू पोहचविणे इत्यादी सहीतचे भरावेत व त्यात कोणत्याही कारणास्तव वाढ देय राहणार नाही.
- ५) संपूर्ण काम समाधानकारक रित्या पूर्ण झाल्या वर कामाचेदेयक / देयके मंजूर दरानुसार व नियमानुसार वजावटी करून विद्यापीठास सोयीस्कर अशा बँकेच्या धनादेशाद्वारे अदा करण्यात येईल.
- ६) नियमानुसार लागू असणारा वस्तू व सेवा कर स्वतंत्ररित्या अदा करण्यात येईल.


कार्यकारी अभियंता



Removing old & damaged flooring and installing new flooring on 2nd floor of Bopodi Competitive Exam Training Center

Sr. No.	Description	Quantity	Unit	Rate	Amount
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	270.00	Sqm		
2	Removing lime or lean cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.	270.00	Sqm		
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	27.00	Cum		
4	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	270.00	Sqm		
5	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete.	27.00	Cum		
TOTAL					