



यशवंतराव चव्हाण महाराष्ट्र मुक्त विद्यापीठ
ज्ञानगंगोत्री, गंगापूर धरणाजवळ, गोवर्धन, नाशिक - 422 222.
दूरध्वनी (0253) 2230072 (कुल.कार्या) 2231714/15, 2230227
[Visit us on at <http://ycmou.digitaluniversity.ac>]

जावक क्र. : UWD/2025-26/1700

दिनांक : 09/02/2026

प्रति,

विषय : विद्यापीठाच्या छत्रपती संभाजीनगर विभागीय केंद्र येथील प्रशासकीय कार्यालय व विभागीय संचालक बाथरूम इ. दुरुस्तीचे कामे करणे बाबत...

महोदय,

विद्यापीठाच्या छत्रपती संभाजीनगर विभागीय केंद्र येथील प्रशासकीय कार्यालय व विभागीय संचालक बाथरूम इ. दुरुस्तीचे कामे करणे बाबत या कामासाठी खाली नमुद केलेल्या अटी व शर्तीनुसार सोबत जोडलेल्या कामाचे दरपत्रक मागविण्यात येत आहे.

विषयांकीत कामाच्या अटी व शर्ती खालील प्रमाणे असतील.

- 1) प्रत्यक्षात सदरकामाच्या ठिकाणी आपण पाहणी करून आपण आपल्या संस्थेच्या लेटरहेडवर दरपत्रक भरून सिलबंद करून दि. 16/02/2026 पर्यंत दुपारी 1.00 वाजेपर्यंत विद्यापीठाच्या बांधकाम कक्षात सादर करावे ही विनंती.
- 2) विषयांकीत काम कार्यादेश मिळाल्यापासून सलग ३० दिवसांत पूर्ण केले पाहिजे.
- 3) कामपूर्ण करण्यास विलंब झाल्यास प्रती दिन रूपये 100/- इतका विलंब आकार आकारण्यात येईल व त्याची वजावट आपणास देय असणाऱ्या रकमेतून करून उर्वरित रकमेचे देयक अदा करण्यात येईल.
- 4) वर उल्लेखलेले दर हे वाहतूक, मजुरी, तूटफूट, वेस्टेज, लोडिंग, अनलोडिंग, विद्यापीठामध्ये वस्तू पोहचविणे इत्यादी सहीतचे भरावेत व त्यात कोणत्याही कारणास्तव वाढ देय राहणार नाही.
- 5) संपूर्ण काम समाधान कारकरित्या पूर्ण झाल्या वर कामाचे देयक/ देयके मंजूर दरानुसार व नियमानुसार वजावटी करून विद्यापीठास सोयीस्कर अशा बँकेच्या धनादेशाद्वारे अदा करण्यात येईल.
- 6) नियमानुसार लागू असणारा वस्तू व सेवा कर स्वतंत्ररित्या अदा करण्यात येईल.

कार्यकारी अभियंता

Yashwantrao Chavan Maharashtra Open University, Nashik.

Name of Work:-

Renovation of Computer lab, Repairs and Maintenance work of Regional Director toilet etc. at Chh.Sambhaji Nagar RC

Schedule B

Sr.No	Ref.No.- SSR 22- 23	Description	Qty	Unit	Rate	Amount
1	23.07	Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. One Number : As directed by Engineer-in-charge.(Labour only)	1.00	MT		
2	38.04	Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 Kilogram/sq.m.).Labour only	45.00	Sqm		
3	38.26	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	45.00	Sqm		
4	33.36	Providing and fixing machine cut mirror polished 18 mm to 20 mm thick telephone black granite / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone partition with full moulding the edges etc. complete . Both side polish	20.07	Sqm		

5	33.68	Providing and laying telephone black / Amba White / Cadburybrown / Ruby red / Ocean Brown granite stone of 18 to 20 mm thick for door frame/ dado/ window boxing etc. On C.M. 1:6 including filling joints with polymer base filler nosing/moulding the sharp edges wherever necessary, curing, etc. complete.	2.69	Sqm		
6	40.08	Providing and Fixing mat finish stainless steel (of 302 grade) railing with top pipe of 50 mm dia. and vertical pipe of 38 mm dia at 0.60 m c/c or as required and horizontal pipes of 25 mm dia in three rows, all pipes of 2 mm thick including buffing,fabricating fixtures and fastening including pipe base of appropriate diameter and ball base of 75 mm dia above newel post of 75 mm diameter etc. complete (Prior approval of sample and brand by Ex.Engineer is necessary before use)	3.20	Rmt		
7	54.30	Procurement, Supply, Installation of required height Sign Board to have a clear and legible visibility, made with 150mm x 150mm size RCC Pole of M30 grade - 8ft height and EPS panel of thickness 75mm having size5 ft Horizontal X 4 ft. vertical. The base will be grouted with a M20 grade Plain Cement concrete foundation of size 600mm x 600mm x 750mm etc	2.00	Nos		
8	38.40	Providing and fixing false ceiling with eco-friendly light-weight calcium silicate tiles of spintone surface texture aerolite make or equivalent of size 595mm x 595mm having 15mm thick densified micro look edge and 100% humidity resistance incombustible as per BS 46part IV and thermal conductivity 0.043 w/m 0 KC and NRC 0.50 placed in true horizontal level suspended grid of size 600x600mm made from hot dipped G.I. steel sections ion silhouette profile, rotary stitched double webbed white with 6mm reveal profile (white/black), wherein, main T runner of size 42mmx14mm between main tee 600mm center-to-center and secondary cross T of size 33x14x0.43mm thick of length 600mm long spaced inter-locked at middle of the first crossed T in each panel to form grid of 1200mmx600mm resting on periphery wall Profile wall section 19mm (7+7) x 19mmx0.40thicknesses and laying false ceiling for services like diffusers grills including cutting, making opening for light fittings, fixtures, , smoke detectors etc., wherever required. Main T runners suspended from ceiling with using G.I. soffit cleats of size 25x35x1.6 mm of required length fixed to the ceiling with 6mm dia and 50mm long dash fastener, 4mm dia	60.48	Sqm		

9	36.13	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	129.60	Sqm		
10	36.03	Providing and applying white-wash in two coats on old / new plastered or masonry surfaces and asbestos cement sheets including scaffolding and preparing the surface by brushing and brooming down etc. complete.	129.60	Sqm		
11	21.02	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means	24.15	Cum		
12	21.06	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	24.15	Cum		
13	24.04	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for foundation and bedding / steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	10.75	Cum		

14	27.05	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	8.38	Cum		
15	32.02	Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:3 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete.	25.20	Sqm		
16	32.15	Providing neeru finish to plastered surfaces in all positions including scaffolding and curing etc. complete.	100.80	Sqm		
17	32.26	Providing and fixing chicken mesh of 22 gauge, with about 30 cm. width at the junction of R.C.C members and brick work, of approved quality including fixing mesh in position by necessary drilling in concrete /B.B.masonry and or tying by binding wire etc. complete.	50.00	Rmt		
18	32.11	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	48.00	Sqm		
19	32.32	Providing and applying Texture plaster with finishing with texture material of approved make in 3 to 4 millimeter thickness on previously plastered surface, including Plaster Groove 6mm thickness or Tape Grooves 35 to 45 mm thickness or as required, in all position including preparing the surface, scaffolding etc. complete.	100.00	Sqm		
20	32.33	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	100.00	No.		
21	32.34	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.	93.60	Rmt		

22	33.40	Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete.	6.00	Sqm		
23	33.41	Providing and laying vitrified mirror / glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 (group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete	34.70	Sqm		
24	46.19	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	34.70	Sqm		
25	46.40	Removing urinal pans or wash hand basins with frame including disconnecting the sanitary and water supply connections, removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc complete	1.00	Nos		
26	46.41	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pan removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc. carefully and throwing	1.00	Nos		
27	31.05	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	6.00	Sqm		
28	31.06	Providing waterproof plaster in W.C. and bath 12 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of 1 Kilogram. per bag of cement of approved make and manufacturer and curing etc. complete. (Excluding Tiles) (As directed by Engineer in Charge)	34.50	Sqm		

29	42.86	Providing and fixing European type wall-hung white water closet of approved make with push valve concealed type with cover plate 32mm size of approved make including soil pipe, vent pipe up to outside face of wall ,100mm dia. G.I. plug bend inlet pipe all fittings, cutting and making good walls, floors etc. complete.	1.00	Nos		
30	41.69	Providing and fixing White glazed with bottle trap earthenware Wash Hand Basin of 55x40 cm size including cold water pillar taps, brackets, rubber plugs and brass chain, stop tap, chromium plate bottle trap and necessary pipe connections including UPAC waste pipe and trap upto the outside face of the wall, making good the damaged surface, testing etc. complete.	1.00	Nos		
31	48.06	Providing and Laying factory made coloured chamfered edge Cement concrete grass paver blocks of required strength,thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine aggregate (natural sand/crushed sand VSI grade finely washed etc.), compacting and proper embedding/laying of inter locking paver blocks into the fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) bedding layer through vibratory compaction by using plate vibrator, filling the joints with fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) and cutting of paver blocks as per required size and pattern, finishing and sweeping extra fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) and complete as per manufacturer specifications & direction of Engineer-in-Charge. 60mm thick CC paver block of M-35 grade concrete with approved colour and design & pattern.(Labour Only)	100.00	Sqm		

32	48.06	Providing and Laying factory made coloured chamfered edge Cement concrete grass paver blocks of required strength,thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine fine aggregate (natural sand/crushed sand VSI grade finely washed etc.), compacting and proper embedding/laying of inter locking paver blocks into the fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) bedding layer through vibratory compaction by using plate vibrator, filling the joints with fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) and cutting of paver blocks as per required size and pattern, finishing and sweeping extra fine aggregate (natural sand/crushed sand VSI grade finely washed etc.) and complete as per manufacturer specifications & direction of Engineer-in-Charge. 60mm thick CC paver block of M-35 grade concrete with approved colour and design & pattern.	100.00	Sqm		
33	40.01	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/ One Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.	4.50	Sqm		
34	39.09	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.	1.89	Sqm		
35	LR-36	Mazdoor - Unskilled Heavy Male	40.00	Day		
Total Amount						
Contractor Sign/Stamp						