



यशवंतराव चव्हाण महाराष्ट्र मुक्त विद्यापीठ  
ज्ञानगंगोत्री, गोवर्धन, नाशिक-४२२२२२

मुद्रित नं. (०२५४)२२३००१९२, (ए. ए. ए. ए.) २५३२४६०/२५, २२३४७९८, २२३०००७२

जा. क्र. : UWD/2025-26/1771

दि. : 12/03/2026

प्रति,

-----  
-----

**विषय- विद्यापीठ परिसरात इलेक्ट्रिकल जेईकल चार्जिंग स्टेशन उभारणे...**

प्रतोदय,

विद्यापीठ परिसरात इलेक्ट्रिकल जेईकल चार्जिंग स्टेशन उभारणे या कामासाठी खाली नमुद केलेल्या अटी व शर्ती नुसार सोबत जोडलेल्या कामाचे दरपत्रक मागविण्यात येत आहे.

**विषयांकीत कामाच्या अटी व शर्ती खालील प्रमाणे असतील.**

- १) प्रत्यक्षात सदर कामाच्या ठिकाणी आपण पाहणी करून आपण आपल्या संस्थेच्या व्हेटरेडवर दरात्रक भरून सिलबंद करून दि.----- पर्यंत दुपारी 1.00 वाजेपर्यंत विद्यापीठाच्या वांधकाम कक्षात सावर करावे.
- २) विषयांकीत काम कार्यदिश मिळाल्या पासून सलग 30 दिवसांत पूर्ण केले पाहिजे.
- ३) काम पूर्ण करण्यास विलंब झाल्यास प्रती दिन रुपये 100/- इतका विलंब आकार आकारण्यात येईल व त्याची वजावट आपणास देय असणाऱ्या रकमेतून करून उर्वरित रकमेचे देयक अदा करण्यात येईल.
- ४) वर ऊल्लेखलेले वर हे वाहतूक, मजुरी, तूटफूट, वेस्टेज, लोडिंग, अनलोडिंग, विद्यापीठांमध्ये वस्तू पोहचविणे इत्यादी सहीतचे भरावेत व त्यात कोणत्याही कारणास्तव वाढ देय राहणार नाही.
- ५) संपूर्ण काम समाधानकारक रित्या पूर्ण झाल्या वर कामाचे देयक / देयके मंजूर दसनूसार व नियमानुसार वजावटी कलून विद्यापीठास सोयीस्कर अशा बँकेच्या धनादेशाद्वारे अदा करण्यात येईल.
- ६) नियमानुसार लागू असणारा वस्तू व सेवा कर स्वतंत्ररित्या अदा करण्यात येईल.

  
Executive Engineer

**विद्यापीठ परिसरात इलेक्ट्रिकल व्हेईकल चार्जिंग स्टेशन उभारणे**

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Manual Means	39.00			
2	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Manual Means	38.75			
3	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	29.90			
4	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	21.73			

5	<p>Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. One Number : As directed by Engineer-in-charge.</p>	1.82			
6	<p>Providing and fixing colour coated Zinalume ( R ) AZ150 ( min 150 gms/sq.mt. total on each side ) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness ( BMT ) (0.5 mm TCT ), Hi-strength steel with min.550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND ( R ) steel quality super durable polyester paint coat ( with inorganic pigment). The paint shall have a total coating thickness of nominal 35 um, comprising of nominal 25 um exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with subtle square fluting in the five pan at nominal 180-250 mm center- to-center. The end rib shall be designed for anti-capillary groove. and return leg. The feed material should have coil manufacturers product details marked a regular interval. Including fasteners with min. fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. complete. (weight of profile 4.52 Kilogram/ One Square Metre)</p>	127.50			

7	<p>Providing and fixing factory made Hydraulically pressed Mechanically vibrated and compacted precast inter locking cement concrete paving blocks 80MM thick in M-40 grade of approved size and shape for City streets, small /medium market roads, low volume roads, utility cuts on arterial roads etc. as specified and as per IS 15658:2006 including cost of all materials, manufacturing, curing, transportation of blocks to work site including loading, unloading and stacking as directed, laying paving blocks in position over prepared bed of natural sand / crushed sand of 50 mm thickness including necessary excavation in all stratas, spreading blinde of fine sand over the prepared bed, compacting blocks by plate vibrator etc. complete.</p>	127.50			
8	<p>Providing, laying and fixing P.V.C. pipe of 75mm dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.</p>	10.00			
9	<p>Providing second class Burnt Brick masonry with conventional / I.S. type bricks in cement mortar 1:4 including scaffolding, racking out joints and watering etc. in pillar of rectangular shapes as shown in the drawings or as directed complete.</p>	6.80			
10	<p>Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.</p>	15.56			

11	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	46.76			
12	Providing, laying and fixing P.V.C. pipe of 110 mm. dia. with fittings such as bends, tees, reducers, clamps, etc. including necessary excavation, trench filling etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	10.00			
13	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.	15.56			
TOTAL					